LINX The World's First Juniper IX

"Why we did it...and what happened!"

Derek Cobb, LINX CTO NANOG54 – March 2012



Content

- 1. About LINX
- 2. Pre-Juniper
- 3. New architecture
- 4. RFQ and contract agreement
- 5. Design
- 6. Programme
- 7. Lessons learned
- 8. War stories



About LINX: Mission

- Dual mission:
 - -To facilitate Internet interconnection in the UK, especially through public peering
 - To represent our members interests in matters of public policy
- As a neutral, mutually-owned membership association
 - –With over 400 members from 50 countries around the world



About LINX: Members









About LINX: Networks (Jan 11)

- 2x independent n*10G Layer 2 Ethernet rings (Brocade & Extreme switches), IPv4/6 dual stack
- Private Interconnect over LINX managed fibre or systems at many sites and between many sites





About LINX: Statistics

- ~400 members
- Total traffic >1.8+ Tb/sec (includes private peering)
- 80% of global routing table
- 876 member ports
- 415x10G member ports





New architecture

- We had realised that our ring-based architecture wasn't scaling well
- We had done the design work on a new architecture in 2010
- We had chosen VPLS as the new design for our primary peering LAN
- We had gained membership agreement to the new architecture in 2010
- Proof of concept work began in 2010 ahead of RFQ in 2011



RFQ

- Juniper and Brocade selected as candidates for VPLS LAN replacement
 - -POC testing in Q1
 - -RFQ in Q2
- LINX Board award contract to Juniper on 15 June
 - -2 year design agreed to support 100% growth by end 2012
 - –Initially MX based with PTX introduction to core in 2012



Contract agreement

- Joint LINX/Juniper sign-off on HLD, LLD & migration plan
 - Juniper professional services and resident engineer contracted
 - -Staging of network prior to deployment
 - –Juniper resident engineer and enhanced TAC support during migration
 - -30 day retention after final site cut-over



Juniper LAN Design





Design Outline





Design - Link and Node Protection





Design – Load Balancing

Example of load-balancing over LSPs and AEs

routing options : pplb *	multiple lsps to end point	AE further hashing of traffic (L3/L4) flows
<pre>routing-options { forwarding-table { export pplb; indirect-next-hop; } policy-options { policy-statement pplb { then { load-balance per-packet; accept; } } }</pre>	label-switched-path e1.thn-to-c1.thw-1 { to 10.0.0.7; node-link-protection; primary Primary-Path { admin-group include-any [ne-nc-1a north1-a]; } }	
	label-switched-path e1.thn-to-c1.thw-2 { to 10.0.0.7; node-link-protection; primary Primary-Path { admin-group include-any [ne-nc-1b north1-b]; } }	



* per flow, not per-packet



Programme

We're a 35 person company with 13 engineers not used to doing stuff this big, so we...

- •Hired a proper programme manager with a track record
- •Formed a steering board with clearly defined responsibilities
- •Built a clearly defined programme with milestones for:
 - High level design and proof of concept
 - Low level design and detailed configuration
 - Operational Readiness Testing (the network works)
 - Acceptance into Service (network, systems and processes are ready)
 - Migration
 - Decommissioning
- Held weekly programme reviews
- •Set up collaboration and sign-off with Juniper at each stage
- •Built a clear communication process with LINX members



Programme Plan

		Timeline								
Workpack	Activity	May-11	Jun-11	Jul-11	Aug-11	Sep-11	Oct-11	Nov-11	Dec-11	
Architecture Refresh Programme	Brocade Stabilisation (H/W Recall)		X	24-Jun						
	Brocade Additional Cards		,		31-Jul					
	MRV Optical Core Build			★ 2	5-Jul					
	MRV Optical Core Accepted into Service			\overleftrightarrow	01-Aug					
	MRV Optical Edge Accepted into Service and Traffic Migrations					30-Aug				
	Juniper Low Level Design, Configuration and Functional Testing			\overleftrightarrow	22-Jul					
	Juniper Core Staging			\overleftrightarrow	29-Jul					
	Juniper Core Accepted into Service				Δ	19-Aug				
	Juniper Edge Staging				\overleftrightarrow	22-Aug				
	Juniper to Brocade Lan Interconnect					31-Aug				
	Systems Development and Delivery					19-Aug				
	Systems Acceptance into Service					31-Aug				
	Juniper Edge Accepted into Service and Member Migrations						\overleftrightarrow	20-Oct		
	30 Days Stable Running								21-Nov	
	Brocade Decommission							$\overrightarrow{\mathbf{x}}$	21-Nov	
	Programme Closure								21-Nov	



So What Did We Do Well?

- We came in on time!
- No unplanned downtime!
- We showed the value of close collaboration with Juniper
- We showed we have some good engineers
- We showed a high level of commitment
- We supported each other and worked as one team
- We learned from an early near-miss!
- Our preparation for the major sites was meticulous and paid off
- We communicated well but sometimes we had to think about it!



What Weren't We So Good At?

- We didn't manage space and power well enough
 - -2 core sites needed late changes
 - -drove additional cost and risk into programme
- We weren't managing our relationships with Data Centre owners
 - -day-to-day is fine but anything else seemed to need CEO escalation
- Our technology roadmaps need to convert to real plans

 programme was too time constrained, increasing risk and
 stress to team



What Weren't We So Good At?

- We need to be better at forecasting
 - -be better prepared and less reactive
 - –better at budget forecasting
 - -we need to manage the order pipeline better
- Our communications can be improved
 - migration web site and weekly updates appreciated by members
 - –maintenance announcements were good, but clearly didn't reach all the right people!
 - –migration ticket updates were appreciated by members



And the Final Summary is?

- Programme approved 14 June
- Low level design and ORT 22 July
- Build complete and Acceptance into Service 22 September
- Migration started 27 September
- Migration completed 29 October
 - -10 sites
 - -110 x 100 Mb/s ports
 - –196 x 1GB/s ports
 - -277 x 10 Gb/s ports
 - 700GB/s peak traffic



Migration War Stories











Connectors





More Patching



Some numbers: •1576 ports connected on Juniper devices •around 900 are ISL ports •around 500 are connected to DWDM links



Junos

- PoC testing done on 10.4R1 (early 2011)
- Final testing done on 10.4R5 (pre-staging)
- During staging, upgrade to 10.4R6 following BGP related defect
- Upgrade to 10.4R7.5 after first migration (Load-balancing related issues)





Current Juniper Capacity

- ~400 members connected
- Current traffic peak ~1Tb/s
- End 2012 design 1.4Tb/s
- Current potential maximum MX edge capacity 9.6Tb/s
- Current potential maximum MX core capacity 3.2Tb/s –PTX upgrade increases potential to approx 9Tb/s in 2013
- No architectural limits to scaling beyond these figures



What's next?

2012

•Evolution of Phase 1 design and protection of investment

•PTX5000 implemented at core Telehouse sites (THN and THW)

- •MX fabric upgrades allow full line rate use of 16x 10 Gb/s cards •Controlled introduction of 100Gb/s member access on MX
- •Review of transport layer to support 100Gb/s
- •sFlow early release on MX in 2H 2012
- •Committed for release in Q1 2013

2013

Review of PTX 3000 at core sites at RBX and RBS
Review of Qfabric for Telehouse sites
sFlow fully supported on MX



Thank you... and any questions!

